

## AGAR NIGAM MATHURA-VRINDAVAN, MATHURA

## ESTIMATE

295 नं. 5  
 मं. सं. 215 गोरखपुरा अंचलिक निस. उ. सं. अंतर्गत  
 काम

Particulars of Item	Nos	Detail			Quantity	Rate / Unit (Rs)	Unit	Amount (Rs)
		L (M)	B (M)	H/D (M)				
1. P.C.C. execution in ordinary soil including all comp. etc	1x1	5.00	1.20	0.75	4.50 m <sup>3</sup>	130.0	m <sup>3</sup>	585.00
2. Blaying 1:5:10 cement and stone ballast all comp. etc -	1x1	5.00	1.20	0.12	0.72 m <sup>3</sup>	3900.0	m <sup>3</sup>	2,808.00
3. 1750 class Blw in 1:4 off fine sand including all comp. etc	1x1	5.00	1.15	0.08	0.46 m <sup>3</sup>			
	1x2	5.00	0.35	0.85	2.97 m <sup>3</sup>			
					3.43 m <sup>3</sup>			15675.00
				Say	3.50 m <sup>3</sup>	4570.0	m <sup>3</sup>	15,995.00
4. P.C.C. 1:2:4 cement and stone grit all comp. etc	1x2	5.00	0.35	0.05	0.17 m <sup>3</sup>			986.00
				Say	0.20 m <sup>3</sup>	5800.0	m <sup>3</sup>	1,160.00
5. 12 mm thick plaster in 1:4 off fine sand including all comp. etc	1x1	5.00	2.15	-	10.75 m <sup>2</sup>	140.0	m <sup>2</sup>	1505.00
6. R.C.C. slab in 1:1 1/2:3 cement and stone grit all comp. etc	1x1	5.00	1.15	0.15	0.86 m <sup>3</sup>			7181.00
				Say	0.90 m <sup>3</sup>	8350.0	m <sup>3</sup>	7,515.00
								<del>99,568.00</del>

99,568.00  
 99,568.00

