

# NAGAR NIGAM MATHURA-VRINDAVAN, MATHURA

## ESTIMATE

of work

प्रा.सं-4 मथुरा नगर निगम के अन्तर्गत विभिन्न सुशान्ति परियोजनाओं के अन्तर्गत कार्य

Sl. No.	Particulars of Item	Nos	Detail			Quantity	Rate/Unit (Rs)	Unit	Amount (Rs)
			L (M)	B (M)	H/D (M)				
	Excavation in ordinary soil depth 1.50m and below with 10% comp.								
		1x1x15.00	0.60	0.60		= 5.40 m <sup>3</sup>			
		1x1x7.00	0.60	0.45		= 1.89 m <sup>3</sup>			
		1x1x12.00	0.60	0.60		= 4.32 m <sup>3</sup>			
						11.61 m <sup>3</sup>	130	1509.30	
	1:1.5 cement sand and 40mm bit stone aggregate								
		1x1x15.00	0.60	0.10		= 0.90 m <sup>3</sup>			
		1x1x7.00	0.60	0.10		= 0.42 m <sup>3</sup>			
		1x1x12.00	0.60	0.10		= 0.72 m <sup>3</sup>			
						2.04 m <sup>3</sup>	2400	4896.00	
	1:5 cement sand and 40mm bit stone aggregate								
		1x1x15.00	0.60	0.08		= 0.72 m <sup>3</sup>			
		1x1x15.00	0.23	0.45		= 3.10 m <sup>3</sup>			
		1x1x7.00	0.60	0.08		= 0.33 m <sup>3</sup>			
		1x2x7.00	0.23	0.28		= 0.90 m <sup>3</sup>			
		1x1x12.00	0.60	0.08		= 0.58 m <sup>3</sup>			
		1x2x12.00	0.23	0.45		= 2.48 m <sup>3</sup>			
		1x1x6.00	0.23	2.50		= 3.45 m <sup>3</sup>			
		1x2x3.50	0.23	0.28		= 0.45 m <sup>3</sup>			
		2x3x15.00	0.23	0.45		= 9.32 m <sup>3</sup>			
		2x1x8.40	0.23	0.28		= 1.15 m <sup>3</sup>			
		1x1x20.00	0.12	0.55		= 0.78 m <sup>3</sup>			
		2x1x15.50	0.23	0.28		= 2.00 m <sup>3</sup>			
						28.26 m <sup>3</sup>	4570.00	115438.20	
								98.12843.50	



